



Project Key Facts

Operator
Woodside

Client
Transfield Worley Woodside Alliance

Location
Carnarvon Basin, Western Australia

Value
AUD 2.4 million (2009)

Contract Period
July 2008 - August 2009

Hours/Safety Statistics
Not Available

Peak Manning
Not Available

AGC's scope of work included the fabrication and assembly of the 120 tonne protection structure and mud mats, fabrication and installation of free issue pipe work, installation of the Non Return Valve (NRV), assembly, coating, testing, system integration test (SIT) assistance, transport and delivery to load out facility at the Australian Marine Complex at Henderson, Western Australia.

This assembly is known as the Pluto Trunkline Non Return Valve (NRV) Skid.

The components of the NRV skid assembly included in this scope of work comprised the following:

- 1 off 36" valve
- 1 off 36" swing check valve
- 1 off 2" double block and bleed valve
- 36", 6" and 2" pipe work and fittings
- NRV structure
- ESCM and electric drive for swing check valve and associated jumpers/leads

